ABSTRACT

Water Resources Department – Announcement made by the Hon'ble Minister for Water Resources for 2022-2023- Rehabilitation of 50 Minor Irrigation Tanks in Sivagangai and Tiruppur Districts at an estimated cost of Rs.32.4274 crore - Administrative and Financial Sanction accorded - Orders issued

- - - -

than 40 Ha) and under the control of Rural development department (ayacut having less than 40 Ha) by the Government of Tamil Nadu. As per G.O.No. 939, Public Works Department, Dated:17.05.1991 the Tanks having ayacuts below 40 Ha have to be standardized and handed over to Rural Development Department.

b). The Ex-Zamin Tanks have lost their functioning due to their eroded bunds, dilapidated sluices, weir and silted up Tank bed. Rain water is the main source of these ex-Zamin Tanks and receives water mainly from its own catchment area only. Due to erratic rainfall and non- maintenance of Tanks & its supply channels, the capacity of the Tanks have got reduced considerably. As such, cultivation under these Tanks is affected more and gap in ayacut is getting increased year by year. Moreover, there is scarcity of water for drinking and cattle feeding. Also, ground water table is getting depleted.

c). These Tanks have not been repaired or rehabilitated for the past 3 to 4 decades. Hence, to bring out the Ex-Zamin Tanks to their standards, it is now proposed to rehabilitate the Tanks. The standardization works includes work such as strengthening of Tank bund, reconstruction of sluices, weir and providing recharging shaft etc. Ayacuts under the above Tanks will get benefitted, besides fulfilling the domestic requirement and improve the Ground Water Tank.

d). The details of Tanks are as follows:-

1. Standardisation of Kothangudi Ex-Zamin Tank in Poosalagudi Village of Kannangudi Block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.53 Crore

The Kothangudi Tank is one among the Ex-Zamin Tanks situated in Poosalagudi Village of Kannangudi block in Devakottai Taluk of Sivagangai District. This Tank is located at 9°56'10" Latitude and 78°37'15" Longitude. The registered ayacut of the Tank is 23.81.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1300 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of length 9.00 m.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice Nos 1, 2 & 3 for 10 m length each.

2. Standardisation of Lekkamari Ex-Zamin Tank in Hanumanthangudi Village of Kannangudi Block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.85 Crore

The Lakkamari Tank is one among the Ex-Zamin Tanks situated in Hanumanthangudi Village of Kannangudi block in Devakottai Taluk of Sivagangai District. This Tank is located at 10°07'20" Latitude and 78°49'40" Longitude. The registered ayacut of the Tank is 22.87.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1850 m.
- Reconstruction of Sluice 5 Nos.
- Reconstruction of weir of 10.50 m length.
- Desilting of supply channel for a length of 850 m.
- Lining to field channel of sluice.

3. Standardisation of Pallivayal Tank in Iruvinivayal Village of Kannangudi block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.67 Crore

The Pallivayal Tank is one among the Ex-Zamin Tanks situated in Iruvinivayal Village of Kannangudi block in Devakottai Taluk of Sivagangai District. This Tank is located at 10°07'20" Latitude and 78°49'40" Longitude. The registered ayacut of the Tank is 20.02.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1350 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 19.50 m length.
- Desilting of supply channel for a length of 950 m.
- Lining to field channel of sluice.

4. Standardisation of Valayanvayal Tank in Kandiyur Village of Devakottai block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.56 Crore

The Valayanvayal Tank is one among the Ex-Zamin Tanks situated in Kandiyur Village of Devakottai block in Devakottai Taluk of Sivagangai District. This Tank is located at 10°07'20" Latitude and 78°49'40" Longitude. The registered ayacut of the Tank is 32.01.6 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1600 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 10.40 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

5. Standardisation of Maruthani Ex-zamin Tank in Eluvankottai Village of Devakottai block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.78 Crore

The Maruthani Tank is one among the Ex-Zamin Tanks situated in Eluvankottai Village of Devakottai block in Devakottai Taluk of Sivagangai District. This Tank is located at 10°07'20" Latitude and 78°49'40" Longitude. The registered ayacut of the Tank is 22.27.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1930 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 27.10 m length.
- Desilting of supply channel for a length of 900 m.
- Lining to field channel of sluice.

6. Standardisation of Kothanikottai ex-zamin Tank in Vengalur Village of Devakottai block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.73 Crore

The Kothanikottai Tank is one among the Ex-Zamin Tanks situated in Vengalur Village of Devakottai block in Devakottai Taluk of Sivagangai District. This Tank is located at 10°00'54" Latitude and 78°50'42" Longitude. The registered ayacut of the Tank is 26.78.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1950 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 17.36 m length.
- Desilting of supply channel for a length of 750 m.
- Lining to field channel of sluice.

7. Standardisation of Thaludhanur ex-zamin Tank in Kurunthanakottai Village of Devakottai block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.73 Crore

The Thaludhanur Tank is one among the Ex-Zamin Tanks situated in Kurunthanakottai Village of Devakottai block in Devakottai Taluk of Sivagangai District. This Tank is located at 9°54'05" Latitude and 78°20'06" Longitude. The registered ayacut of the Tank is 28.74.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1600 m.
- Reconstruction of Sluice 5 Nos.
- Reconstruction of weir of 9.50 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

8. Standardisation of Periyanayagivayal Ex-zamin Tank in Sirumaruthur Village of Devakottai block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.41 Crore

The Periyanayagivayal Tank is one among the Ex-Zamin Tanks situated in Sirumaruthur Village of Devakottai block in Devakottai Taluk of Sivagangai District. This Tank is located at 10°07'20" Latitude and 78°49'40" Longitude. The registered ayacut of the Tank is 18.15.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1050 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 6.00 m length.
- Desilting of supply channel for a length of 950 m.
- Lining to field channel of sluice.

9. Standardisation of Arasuvayal Manjaneer Tank in Ambakudi Village of Karaikudi block in Karaikudi Taluk of Sivagangai District for Estimate amount of Rs.0.77 Crore

The Arasuvayal Manjaneer Tank is one among the Ex-Zamin Tanks situated in Ambakudi Village of Sakkottai block in Karaikudi Taluk of Sivagangai District. This Tank is located at 10°07'20" Latitude and 78°49'40" Longitude. The registered ayacut of the Tank is 18.56.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 2575 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 27.00 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

10. Standardisation of Kalluvayal Pudu Ex- zamin Tank in Kallupatti Village of Kallal block in Devakottai Taluk of Sivagangai District for Estimate amount of Rs.0.52 Crore

The Kalluvayal Pudu Tank is one among the Ex-Zamin Tanks situated in Kallupatti Village of Kallal block in Devakottai Taluk of Sivagangai District. This Tank is located at 9°59'18" Latitude and 78°48'37" Longitude. The registered ayacut of the Tank is 31.98.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 980 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 8.50 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

11. Standardisation of Karuvi Ex-Zamin Tank in Kallangudi Village of Sakkottai Block in Karaikudi Taluk of Sivagangai District for Estimate amount of Rs.0.72 Crore

The Karuvi Tank is one among the Ex-Zamin Tanks situated in Kallangudi Village of Sakkottai block in Karaikudi Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 25.23.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 980 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 14.60 m length.
- Desilting of supply channel for a length of 1200 m.
- Lining to field channel of sluice.

12. Standardisation of Venkata Ex-Zamin Tank in Sothukudi Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District for Estimate amount of Rs.0.70 Crore

The Venkata Tank is one among the Ex-Zamin Tanks situated in Sothukudi Village of Ilayangudi block in Ilayangudi Taluk of Sivagangai District. This Tank is located at 9°55′30″ Latitude and 78°36′10″ Longitude. The registered ayacut of the Tank is 38.90.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 2000 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 25.00 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

13. Standardisation of Valayanenthal Ex-Zamin Tank in Karunchuthi Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District for Estimate amount of Rs.0.74 Crore

The Valayanendal Tank is one among the Ex-Zamin Tanks situated in Karuchuthi Village of Ilayangudi block in Ilayangudi Taluk of Sivagangai District. This Tank is located at 9°55′30″ Latitude and 78°36′10″ Longitude. The registered ayacut of the Tank is 19.13.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 2000 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 17.00 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

14. Standardisation of Chithalangudi Ex-Zamin Tank in Kalaikulam Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District for Estimate amount of Rs.0.69 Crore

The Chithalangudi Tank is one among the Ex-Zamin Tanks situated in Kalaikulam Village of Ilayangudi block in Ilayangudi Taluk of Sivagangai District. This Tank is located at 9°43′08″ Latitude and 78°31′51″ Longitude. The registered ayacut of the Tank is 23.22.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1300 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 25.00 m length.
- Desilting of supply channel for a length of 500 m.
- Lining to field channel of sluice.

15. Standardisation of Karaikudi Ex-Zamin Tank in Keelayur Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District for Estimate amount of Rs.0.54 Crore

The Karaikudi Tank is one among the Ex-Zamin Tanks situated in Keelayur Village of Ilayangudi block in Ilayangudi Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 25.41.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1030 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 3.00 m length.
- Desilting of supply channel for a length of 500 m.
- Lining to field channel of sluice.

16. Standardisation of Sathiyendal Ex-Zamin Tank in Vadakku Ilayangudi Village in Ilayangudi Taluk of Sivagangai District for Estimate amount of Rs.0.48 Crore

The Sathiyendal Tank is one among the Ex-Zamin Tanks situated in North Ilayangudi Village of Ilayangudi block in Ilayangudi Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 16.97.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 750 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of pipe culvert.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

17. Standardisation of Pudukulam Ex-Zamin Tank in North Keeranur Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District for Estimate amount of Rs.0.52 Crore

The Pudukulam Tank is one among the Ex-Zamin Tanks situated in North Keeranur Village of Ilayangudi block in Ilayangudi Taluk of Sivagangai District. This Tank is located at 9°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 22.33.9 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1900 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 8.20 m length.
- Desilting of supply channel for a length of 1500 m.
- Lining to field channel of sluice.

18. Standardisation of Kattupudu Ex-Zamin Tank in Aranmanai Siruvayal Village of Kallal Block in Karaikudi Taluk of Sivagangai District for Estimate amount of Rs.0.59 Crore

The Kattupudu Tank is one among the Ex-Zamin Tanks situated in Aranmanai Siruvayal Village of Kallal block in Karaikudi Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 14.38.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1800 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 14.50 m length.
- Desilting of supply channel for a length of 800 m.
- Lining to field channel of sluice.

19. Standardisation of Kadambankulam Ex-Zamin Tank in Kallal Village of Kallal Block in Karaikudi Taluk of Sivagangai District for Estimate amount of Rs.0.50 Crore

The Kadambankulam Tank is one among the Ex-Zamin Tanks situated in Kallal Village of Kallal block in Karaikudi Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude The registered ayacut of the Tank is 16.56.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 750 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 21.00 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

20. Standardisation of Vengai Ex-Zamin Tank in Kallal Village of Kallal Block in Karaikudi Taluk of Sivagangai District for Estimate amount of Rs.0.39 Crore

The Vengai Tank is one among the Ex-Zamin Tanks situated in Kallal Village of Kallal block in Karaikudi Taluk of Sivagangai District. This Tank is located at 10°16′44″ Latitude and 78°28′16″ Longitude. The registered ayacut of the Tank is 11.41.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 850 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 6.00 m length.
- Lining to field channel of sluice.

21. Standardisation of Vellakudi Tank in Marathur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.83 Crore

The Vellakudi Tank is one among the Ex-Zamin Tanks situated in Marathur Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude The registered ayacut of the Tank is 37.66.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1100 m.
- Reconstruction of Sluice 5 Nos.
- Reconstruction of weir of 21.20 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

22. Standardisation of Pappan Ex-Zamin Tank in Purasadi Udaippu Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.75 Crore

The Pappan Tank is one among the Ex-Zamin Tanks situated in Purasadi Udaippu Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 21.61.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 2100 m.
- Reconstruction of Sluice 6 Nos.
- Lining to field channel of sluice.

23. Standardisation of Satharasankottai Ex-Zamin Tank in Mallal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.69 Crore

The Satharasankottai Tank is one among the Ex-Zamin Tanks situated in Mallal Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°50′16″ Latitude and 78°32′58″ Longitude. The registered ayacut of the Tank is 38.84.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 2000 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 23.00 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

24. Standardisation of Minnaranjan Ex-Zamin Tank in Velangulam Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.66 Crore

The Minnaranjan Tank is one among the Ex-Zamin Tanks situated in Velangulam Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 28.39.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1600 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 30.00 m length.
- Desilting of supply channel for a length of 800 m.
- Lining to field channel of sluice.

25. Standardisation of Kilavanoor Ex-Zamin Tank in Pulavanvayal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.64 Crore

The Kilavanoor Tank is one among the Ex-Zamin Tanks situated in Pulavanvayal Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°50′44″ Latitude and 78°32′51″ Longitude. The registered ayacut of the Tank is 34.64.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 2000 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 27.40 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

26. Standardisation of Sathani Periya Ex-Zamin Tank in Vittaneri Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.61Crore

The Sathani Periya Tank is one among the Ex-Zamin Tanks situated in Vittaneri Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 34.64.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1500 m.
- Reconstruction of Sluice 4 Nos.
- Reconstruction of weir of 8.50 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

27. Standardisation of Eattiyarenthal Ex-Zamin Tank in Vettikulam Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.59 Crore

The Eattiyarenthal Tank is one among the Ex-Zamin Tanks situated in Vettikulam Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°50′26″ Latitude and 78°32′21″ Longitude. The registered ayacut of the Tank is 22.85.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1500 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 27.00 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

28. Standardisation of Sirusaananvayal Ex-Zamin Tank in Marathur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.57 Crore

The Siru Sanankanmoi Tank is one among the Ex-Zamin Tanks situated in Marathur Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°53′21″ Latitude and 78°32′02″ Longitude. The registered ayacut of the Tank is 22.51.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1000 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 23.00 m length.
- Desilting of supply channel for a length of 850 m.
- Lining to field channel of sluice.

29. Standardisation of Manthi Ex-Zamin Tank in Nallenthal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.54 Crore

The Manthi Tank is one among the Ex-Zamin Tanks situated in Nallendal Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°16′44″ Latitude and 78°28′16″ Longitude. The registered ayacut of the Tank is 26.14.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1200 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 12.00 m length.
- Desilting of supply channel for a length of 2000 m.
- Lining to field channel of sluice.

30. Standardisation of Kunakodai Ex-Zamin Tank in Siriyur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.51 Crore

The Kunakodai Tank is one among the Ex-Zamin Tanks situated in Siriyur Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 22.92.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1560 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 13.00 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

31. Standardisation of Kurunthangudi Ex-Zamin Tank in Vannikudi Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.49 Crore

The Kurunthangudi Tank is one among the Ex-Zamin Tanks situated in Vannikudi Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 37.75.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1600 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 11.00 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

32. Standardisation of Kandanikarai Ex-Zamin Tank in Sethambal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.48 Crore

The Kandanikarai Tank is one among the Ex-Zamin Tanks situated in Sethambal Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°59′05″ Latitude and 78°38′12″ Longitude. The registered ayacut of the Tank is 31.99.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1500 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 10.00 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

33. Standardisation of Thiranikulam Vadakaruppan Ex-Zamin Tank in Sevaoorani Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.47 Crore

The Thiranikulam Vadakaruppan Tank is one among the Ex-Zamin Tanks situated in Sevaoorani Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 21.56.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1600 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 4.80 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

34. Standardisation of Usilangulam Veeranendhal Ex-Zamin Tank in Nallendhal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.45 Crore

The Usilangulam Veeranendhal Tank is one among the Ex-Zamin Tanks situated in Nallendhal Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°49′20″ Latitude and 78°31′33″ Longitude. The registered ayacut of the Tank is 26.72.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1100 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 14.00 m length.
- Desilting of supply channel for a length of 600 m.
- Lining to field channel of sluice.

35. Standardisation of Vellangudi Ex-Zamin Tank in Sembar Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.40 Crore

The Vellangudi Tank is one among the Ex-Zamin Tanks situated in Sembar Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°55'30" Latitude and 78°36'10" Longitude. The registered ayacut of the Tank is 33.39.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1062 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 5.80 m length.
- Desilting of supply channel for a length of 700 m.
- Lining to field channel of sluice.

36. Standardisation of Pulavar Maruthangudi Periya Ex-Zamin Tank in Marathur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.44 Crore

The Pulavar Maruthangudi Periya Tank is one among the Ex-Zamin Tanks situated in Marathur Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°16'13" Latitude and 78°29'00" Longitude. The registered ayacut of the Tank is 13.40.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1100 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 9.80 m length.
- Desilting of supply channel for a length of 900 m.
- Lining to field channel of sluice.

37. Standardisation of Valaiperuman Ex-Zamin Tank in Siramam Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.43 Crore

The Valaiperuman Tank is one among the Ex-Zamin Tanks situated in Siramam Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°16'13" Latitude and 78°29'00" Longitude. The registered ayacut of the Tank is 26.58.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1285 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 4.50 m length.
- Desilting of supply channel for a length of 1000 m.
- Lining to field channel of sluice.

38. Standardisation of Kittukottai Ex-Zamin Tank in Vannikudi Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.43 Crore

The Kittukottai Tank is one among the Ex-Zamin Tanks situated in Vannikudi Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 22.60.3 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1250 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 7.00 m length.
- Desilting of supply channel for a length of 700 m.
- Lining to field channel of sluice.

39. Standardisation of Ammancheri Ex-Zamin Tank in Sethambal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.42 Crore

The Ammancheri Tank is one among the Ex-Zamin Tanks situated in Sethambal Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 10°07′20″ Latitude and 78°49′40″ Longitude. The registered ayacut of the Tank is 20.13.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1000 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 10.00 m length.
- Desilting of supply channel for a length of 800 m.
- Lining to field channel of sluice.

40. Standardisation of Thenmalathan Ex-Zamin Tank in Siriyur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.41 Crore

The Thenmalathan Tank is one among the Ex-Zamin Tanks situated in Siriyur Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°50′30″ Latitude and 78°33′26″ Longitude. The registered ayacut of the Tank is 24.50.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 1500 m.
- Reconstruction of Sluice 1 Nos.
- Reconstruction of weir of 11.00 m length.
- Desilting of supply channel for a length of 1200 m.
- Lining to field channel of sluice.

41. Standardisation of Kalugadi Ex-Zamin Tank in Sirukanaperi Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District for Estimate amount of Rs.0.40 Crore

The Kalugadi Tank is one among the Ex-Zamin Tanks situated in Sirukanaperi Village of Kalayarkoil block in Kalayarkoil Taluk of Sivagangai District. This Tank is located at 9°49′55″ Latitude and 78°33′02″ Longitude. The registered ayacut of the Tank is 37.64.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 800 m.
- Reconstruction of Sluice 2 Nos.
- Reconstruction of weir of 12.70 m length.
- Desilting of supply channel for a length of 500 m.
- Lining to field channel of sluice.

42. Standardisation of Periyapoongudi Ex-Zamin Tank in Madhagupatti Village of Sivagangai Block in Sivagangai Taluk of Sivagangai District for Estimate amount of Rs.0.51 Crore

The Periyapoongudi Tank is one among the Ex-Zamin Tanks situated in Madhagupatti Village of Sivagangai block in Sivagangai Taluk of Sivagangai District. This Tank is located at 9°56′10″ Latitude and 78°37′15″ Longitude. The registered ayacut of the Tank is 36.62.0 Hectares.

In this estimate, it is proposed to do the following works:-

- Strengthening of Tank bund for a length of 850 m.
- Reconstruction of Sluice 3 Nos.
- Reconstruction of weir of 15.55 m length.
- Lining to field channel of sluice.

II. Rehabilitation of 8 Minor Irrigation Tanks Tiruppur District

a) Noyyal is a Sub basin of River Cauvery in Tamil Nadu which flows into four Districts namely Coimbatore, Tiruppur, Erode and Karur. Noyyal river system originates from Western Ghats and confluences in River Cauvery at Noyyal Village in Karur District. The sub basin area wide spread of about 1440 sq.km. The Noyyal river system in the sub basin has 23 Anicuts, 31 system Tanks and two reservoirs under the maintenance of Water Resources Department. Besides there are 26 Nos of non system Tanks in the Noyyal sub basin which are rain fed Tanks in Coimbatore, Tiruppur and Erode District.

b) All the 8 Tanks proposed under this announcement are one among those non system Tanks located in Tiruppur District. These Tanks have Juliflora jungle and light jungles. The supply channels and the surplus course have obstructions due to the growth of the vegetations and siltation. The surplus weir have been long back.

Scrubs and vegetations have grown over the weir which has dilapilated the structure. The width of the Tank bund is inadequate to the standards in few segments. No Revetment or pitching in the water face slope of the bunds. Siltation has been noticed in some locations of the water spread area. Vegetations with fallen earth and silt in the inlets stream of the Tanks are noticed which would affect the flow of water. Inspection tracks in some of the segments are also not in order. Sluices in the Tank are worn out and not in operation. Hence repair and rectification of these defects in the Tank is mandatory for restoring the Tank.

c) Due to long run and inadequate maintenance, the Tanks require these rehabilitation works to get restored. The rehabilitation works proposed in this project will ensure effective storage and function of the Tanks

d) The details of Tanks are as follows

43. Rehabilitation of Avinashilingampalayam Tank in Avinashi Taluk Of Tiruppur District for Estimate amount of Rs.149.00 Lakhs

The following are the work components proposed in the estimates.

1. Provision for skin wall to the existing damaged weir and apron wearing coat.
2. Repairs to the dilapidated sluices.
3. Replacement of sluice shutter.
4. Strengthening the weakened Tank bund
5. Providing revetment in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
8. Desilting the Tank bed and inlet channel
9. Demarcation of boundaries.
10. Construction of retaining wall in the low lying segments of the inlet stream
11. Provision for Labour welfare fund @1%
12. Provision for advertisement charges.
13. Provision for escalation.
14. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 21.85 hectares will get benefitted.

44. Rehabilitation of Thamaraikulam Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.148.00 Lakhs

The following are the work components proposed in the estimates.

1. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
2. Repairs to the dilapidated weir and sluices.
3. Strengthening the weakened Tank bund.
4. Providing revetment in the u/s of the Tank bund
5. Restoration of Tank inlet streams.
6. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
7. Desilting the Tank bed and inlet channel
8. Demarcation of boundaries.
9. Fencing the boundry along the roadways to curtail public littering.
10. Provision for Labour welfare fund @1%
11. Provision for advertisement charges.
12. Provision for escalation.
13. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 35.04 hectares will get benefitted.

45. Rehabilitation of Punjaithamaraikulam Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.99.00 Lakhs

The following are the work components proposed in the estimates.

1. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
2. Repairs to the dilapidated sluices with rear cistern.
3. Replacement of sluice shutter.
4. Strengthening the weakened Tank bund
5. Providing revetment in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Desilting the Tank bed and inlet channel
8. Demarcation of boundaries.
9. Provision for Labour welfare fund @1%
10. Provision for advertisement charges.
11. Provision for escalation.
12. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 8.09 hectares will get benefitted.

46. Rehabilitation of Pappankulam Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.98.00 Lakhs

The following are the work components proposed in the estimates.

1. Provision for skin wall to the existing damaged weirs and apron wearing coat.
2. Repairs to the dilapidated sluices.
3. Replacement of sluice shutter.
4. Strengthening the weakened Tank bund
5. Providing revetment using cement concrete blocks in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
8. Desilting the inlet channel
9. Demarcation of boundaries.
10. Provision for Labour welfare fund @1%
11. Provision for advertisement charges.
12. Provision for escalation.
13. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 4.86 hectares will get benefitted.

47. Rehabilitation of Kilakulam Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.98.00 Lakhs

The following are the work components proposed in the estimates.

1. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
2. Improvements to the sluices.
3. Erection of sluice shutter.
4. Standardization of Tank bund
5. Providing revetment using cement concrete blocks in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Desilting the inlet channel
8. Construction of retaining wall in the low lying segments of the inlet stream
9. Provision for Labour welfare fund @1%
10. Provision for advertisement charges.
11. Provision for escalation.
12. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 25.49 hectares will get benefitted.

48. Rehabilitation of Karuvalur Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.98.00 Lakhs

The following are the work components proposed in the estimates.

1. Reconstruction of surplus weir
2. Repairs to the dilapidated sluices.
3. Replacement of sluice shutter.
4. Strengthening the weakened Tank bund
5. Providing revetment using cement concrete blocks in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
8. Desilting the inlet channel
9. Demarcation of boundaries.
10. Fencing the Tank boundary near the habitats to prevent public littering.
11. Provision for Labour welfare fund @1%
12. Provision for advertisement charges.
13. Provision for escalation.
14. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 10.12 hectares will get benefitted.

49. Rehabilitation of Kanur Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.139.00 Lakhs

The following are the work components proposed in the estimates.

1. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
2. Improvements to the sluice.
3. Erection of sluice shutter.
4. Standardization of Tank bund
5. Providing revetment using cement concrete block in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
8. Desilting the inlet channel
9. Construction of retaining wall in the low lying segments of the inlet stream
10. Provision for Labour welfare fund @1%
11. Provision for advertisement charges.
12. Provision for escalation.
13. Provision for petty supervision and unforeseen items @2.5%.

By implementing this scheme, an ayacut of about 31.97 hectares will get benefitted.

50. Rehabilitation of Naduvachery Tank in Avinashi Taluk of Tiruppur District for Estimate amount of Rs.100.00 Lakhs

The following are the work components proposed in the estimates.

1. Provision for skin wall to the existing damaged weir and apron wearing coat.
2. Repairs to the dilapidated sluices.
3. Replacement of sluice shutter.
4. Strengthening the weakened Tank bund
5. Providing revetment in the u/s of the Tank bund
6. Restoration of Tank inlet streams.
7. Clearing jungles and juliflora in the inlets, bunds and Tank water spread area.
8. Desilting the inlet channel
9. Demarcation of boundaries.
10. Provision for Labour welfare fund @1%
11. Provision for advertisement charges.
12. Provision for escalation.
13. Provision for petty supervision and unforeseen items @2.5%.

3. The Chief Engineer, Plan Formulation, Water Resources Department has stated that all the above estimates have been prepared based on the Schedule of Rates for the year 2021 - 2022 and mandatory lump sum provisions have been made in all the detailed estimates and requested that Administrative Sanction for the above works may be accorded for Rs 33.43 Crore.

4. The Government, after careful examination, have accepted the above proposal of the Chief Engineer, Plan Formulation, Water Resources Department, restricting the cost of the works to Rs.32,42,74,000/-. Accordingly administrative and financial sanction is accorded for Rehabilitation of 50 Minor Irrigation Tanks in Sivagangai and Tiruppur Districts at an estimated cost of Rs.32,42,74,000/- (Rupees Thirty two Crore forty two lakh and seventy four thousand only) as detailed below

S. No	Name of the work	Restricted amount (Rs. in Crore)
	42 Ex-Zamin Tanks in Sivagangai District	
1.	Standardisation of Kothangudi Ex-Zamin Tank in Poosalagudi Village of Kannangudi Block in Devakottai Taluk of Sivagangai District	0.53
2.	Standardisation of Lekkamari Ex-Zamin Tank in Hanumanthangudi Village of Kannangudi Block in Devakottai Taluk of Sivagangai District	0.85

3.	Standardisation of Pallivayal Ex-Zamin Tank in Iruvinivayal Village of Kannangudi Block in Devakottai Taluk of Sivagangai District	0.67
4.	Standardisation of Valayanvayal Ex-Zamin Tank in Kandiyur Village of Devakottai Block in Devakottai Taluk of Sivagangai District	0.56
5.	Standardisation of Maruthani Ex-Zamin Tank in Eluvankottai Village of Devakottai Block in Devakottai Taluk of Sivagangai District	0.78
6.	Standardisation of Kothanikottai Ex-Zamin Tank in Vengalur Village of Devakottai Block in Devakottai Taluk of Sivagangai District	0.73
7.	Standardisation of Thaludhanur Ex-Zamin Tank in Kurunthanakottai Village of Devakottai Block in Devakottai Taluk of Sivagangai District	0.73
8.	Standardisation of Periyanayagivayal Ex-Zamin Tank in Sirumaruthur Village of Devakottai Block in Devakottai Taluk of Sivagangai District	0.41
9.	Standardisation of Arasuvayal Manjaneer Ex-Zamin Tank in Ambakudi Village of Sakkottai Block in Karaikudi Taluk of Sivagangai District	0.77
10.	Standardisation of Kalluvayal Pudu Ex-Zamin Tank in Kallupatti Village of Kallal Block in Devakottai Taluk of Sivagangai District	0.52
11.	Standardisation of Karuvi Ex-Zamin Tank in Kallangudi Village of Sakkottai Block in Karaikudi Taluk of Sivagangai District	0.72
12.	Standardisation of Venkata Ex-Zamin Tank in Sothukudi Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District	0.70
13.	Standardisation of Valayanenthal Ex-Zamin Tank in Karunchuthi Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District	0.74
14.	Standardisation of Chithalangudi Ex-Zamin Tank in Kalaikulam Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District	0.69
15.	Standardisation of Karaikudi Ex-Zamin Tank in Keelayur Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District	0.54
16.	Standardisation of Sathiyendal Ex-Zamin Tank in Vadakku Ilayangudi Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District	0.48

17.	Standardisation of Pudukulam Ex-Zamin Tank in North Keeranur Village of Ilayangudi Block in Ilayangudi Taluk of Sivagangai District	0.52
18.	Standardisation of Kattupudu Ex-Zamin Tank in Aranmanai Siruvayal Village of Kallal Block in Karaikudi Taluk of Sivagangai District	0.59
19.	Standardisation of Kadambankulam Ex-Zamin Tank in Kallal Village of Kallal Block in Karaikudi Taluk of Sivagangai District	0.50
20.	Standardisation of Vengai Ex-Zamin Tank in Kallal Village of Kallal Block in Karaikudi Taluk of Sivagangai District	0.39
21.	Standardisation of Vellakudi Tank in Marathur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.83
22.	Standardisation of Pappan Ex-Zamin Tank in Purasadi Udaippu Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.75
23.	Standardisation of Satharasankottai Ex-Zamin Tank in Mallal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.69
24.	Standardisation of Minnaranjan Ex-Zamin Tank in Velangulam Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.66
25.	Standardisation of Kilavanoor Ex-Zamin Tank in Pulavanvayal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.64
26.	Standardisation of Sathani Periya Ex-Zamin Tank in Vittaneri Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.61
27.	Standardisation of Eattiyarenthal Ex-Zamin Tank in Vettikulam Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.59
28.	Standardisation of Sirusananvayal Ex-Zamin Tank in Marathur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.57
29.	Standardisation of Manthi Ex-Zamin Tank in Nallenthal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.54
30.	Standardisation of Kunakodai Ex-Zamin Tank in Siriyur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.51
31.	Standardisation of Kurunthangudi Ex-Zamin Tank in Vannikudi Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.49

32.	Standardisation of Kandanikarai Ex-Zamin Tank in Sethambal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.48
33.	Standardisation of Thiranikulam Vadakaruppan Ex-Zamin Tank in Sevaoorani Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.47
34.	Standardisation of Usilangulam Veeranendhal Ex-Zamin Tank in Nallendhal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.45
35.	Standardisation of Vellangudi Ex-Zamin Tank in Sembar Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.40
36.	Standardisation of Pulavar Maruthangudi Periya Ex-Zamin Tank in Marathur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.44
37.	Standardisation of Valaiperuman Ex-Zamin Tank in Siramam Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.43
38.	Standardisation of Kittukottai Ex-Zamin Tank in Vannikudi Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.43
39.	Standardisation of Ammancheri Ex-Zamin Tank in Sethambal Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.42
40.	Standardisation of Thenmalathan Ex-Zamin Tank in Siriyur Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.41
41.	Standardisation of Kalugadi Ex-Zamin Tank in Sirukanaperi Village of Kalayarkoil Block in Kalayarkoil Taluk of Sivagangai District	0.40
42.	Standardisation of Periyapoongudi Ex-Zamin Tank in Madhagupatti Village of Sivagangai Block in Sivagangai Taluk of Sivagangai District	0.51
	8 Minor Irrigation Tanks Tiruppur District	
43.	Rehabilitaion of Avinashilingampalayam Tank in Avinashi Taluk Of Tiruppur District	1.3288
44.	Rehabilitaion of Thamaraikulam Tank in Avinashi Taluk of Tiruppur District	1.3190
45.	Rehabilitaion of Punjaithamaraikulam Tank in Avinashi Taluk of Tiruppur District	0.8853
46.	Rehabilitaion of Pappankulam Tank in Avinashi Taluk of Tiruppur District	0.8744
47.	Rehabilitaion of Kilakulam Tank in Avinashi Taluk of Tiruppur District	0.8710

48.	Rehabilitaion of Karuvalur Tank in Avinashi Taluk of Tiruppur District	0.8813
49.	Rehabilitaion of Kanur Tank in Avinashi Taluk of Tiruppur District	1.2410
50.	Rehabilitaion of Naduvachery Tank in Avinashi Taluk of Tiruppur District	0.8866
	GRAND TOTAL	**32.4274**

5. The expenditure sanctioned in para 4 above shall be debited to the following head of account:- (40.01)

Sl.No.1 to 42 – Rs.24,14,00,000/-

4700 – Capital Outlay on Major Irrigation – 05 - Vaigai Basin – 800 – Other Expenditure - State's Expenditure – AA – Reservoirs – 416 – Major Works - 01 Major Work.

(IFHRMS DPC 4700 – 05 – 800 – AA – 416-01)

Sl. No. 43 to 50 – Rs.8,28,74,000/-

4700 – Capital Outlay on Major Irrigation – 01 – Cauvery Basin – 800 – Other Expenditure - State's Expenditure – AA – Reservoir – 416 – Major Works - 01 Major Work.

(IFHRMS DPC 4700 – 01 – 800 – AA – 416-01)

6. The Chief Engineers of Plan Formulation, Madurai Region and Coimbatore Region, Water Resources Department and District Collectors are requested to complete all rehabilitation works sanctioned in para 4 above before the onset of the North East Monsoon so that sufficient water can be stored in the above water bodies.

7. Necessary additional funds of Rs.32,42,74,000/- will be provided in Revised Estimate / Final Modified Appropriation 2022 – 2023. Pending provision of such funds, the Engineer-in-Chief and Chief Engineer (General), Water Resources Department, Chennai is authorized to draw and disburse the amount sanctioned in para 4 above. However the above expenditure shall be brought to the notice of the Legislative Assembly by specific inclusion in supplementary Estimate 2022 – 2023. The Engineer-in-Chief and Chief Engineer (General), Water Resources Department, Chennai is directed to send necessary proposal for inclusion of this expenditure in Revised Estimate / Final Modified Appropriation 2022 – 2023 and also send necessary draft explanatory note for specific inclusion of this expenditure in the Supplementary Estimate 2022 – 2023 to Finance (BG-I / PW-II) Department at an appropriate time without fail.

8. The Engineers concerned are directed that the details of works executed must be uploaded in the Tamil Nadu Water Resources Information and Management Systems Portal under the Control of Chief

Engineer, Institute of Water Studies, Hydrology and Quality Control to ensure effective data base in the Water Resources Department.

9. This order issues with the concurrence of Finance Department vide its U.O. No.28778/PW-II/2022, dated.22.06.2022 and Additional Sanction Ledger No.451 (Four hundred and fifty one)

(BY ORDER OF THE GOVERNOR)

SANDEEP SAXENA,
ADDITIONAL CHIEF SECRETARY TO GOVERNMENT.

To

The Engineer-in-Chief and Chief Engineer (General), Water Resources Department, Chennai-5.
The Chief Engineer, Plan Formulation, Water Resources Department, Chennai-5.
The Chief Engineer, Water Resources Department, Madurai Region, Madurai.
The Chief Engineer, Water Resources Department, Coimbatore Region, Coimbatore.
The Chief Engineer, Institute of Water Studies, Hydrology and Quality Control, Taramani, Chennai-113.
The District Collector, Sivagangai.
The District Collector, Tiruppur.
The Treasury Officer, Sivagangai.
The Treasury Officer, Tiruppur.
The Pay and Accounts Officer, Madurai.
The Pay and Accounts Officer (East), Chennai-8.
The Principal Accountant General (A&E),Chennai-18.
The Principal Accountant General (Economic and Revenue Sector Audit), Chennai-18.
The Resident Audit Officer, Secretariat, Chennai-9.

Copy to

The Secretary-II to the Hon'ble Chief Minister, Secretariat, Chennai-9.
The Special Personal Assistant to Hon'ble Minister (Water Resources), Chennai-9.
The Finance (P.W.II / B.G.I / BG.II/ W&M-I) Department, Secretariat, Chennai-9.
The Water Resources (OP-II / ISpl.I) Department, Secretariat, Chennai-9.
Stock File / Spare Copy.

// Forwarded by Order //

24/06/2022

Section Officer